

## Addendum

PROJECT: Tirey Hall Art Storage

ADDENDUM # 3

DATE: 10/18/2013

TO: ALL INTERESTED BIDDERS OF RECORD

BID NUMBER: B0022544

This Addendum # 3 forms part of the Contract Documents and modifies the original Bidding Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to acknowledge this addendum may subject Bidder to disqualification.

### GENERAL INFO

1. The last day and time for questions has past. Any further questions cannot be guaranteed consideration and will only be answered at the Owner's discretion.

### SPECIFICATION REVISIONS

1. None

### DRAWING REVISIONS

1. See attached R.E. Dimond Addendum # 3

### QUESTION AND ANSWERS

The follow question was received from Don Jungst from Mezzetta, Inc.

- Q Are we to remove the acoustic ceiling along the length of the partition wall and the ramp wall so that the Type 'I' wall runs to the underside of the concrete deck above or are we to use a double top plate anchored into the exposed concrete beams so that the Type 'I' walls will terminate at the height of the existing ceiling?
- A The full height wall partitions will anchor to the existing concrete beams and existing dropped ceiling system.

The following questions were received from Jeff Strobe from Evan & Ryan

- Q Superior Cabinet was mentioned at the pre-bid as the casework supplier. Are casework specs available or will Superior Cabinets be declared as the supplier for the project?
- A Superior Cabinets of Terre Haute has been designing the cabinets with the P.A.C. department and will the supplier and installer of all of these custom P.A.C. cabinets. These will accounted for as part of the allowance budget. The Archive storage side will be standard metal shelving units to store Banker's Boxes and will be purchased and installed by contractor as part of the remaining allowance budgeted in the project.
- Q Other than HM frames, HM doors, hinges and flush bolts, will any other hardware be required as part of base bid?
- A ISU will be providing all Leverset hardware and strike plates. Contractor will be required to provide for remained needed door hardware such as hinges; flush bolts; silencers; wall and or floor stops. No door closers are required in project.

Q Is plywood floor/wall sheathing or any other lumber to be fire rated?

A Not at this time. Pending what Alternates are accepted we may ask for a proposal after the Bid is Awarded.

OWNER COMMENT

1. The ramps leading to the lower locker rooms will need to have a total running length slope of approximately 30' to meet the less than 10% slope requirement.

End of Addendum # 3

attachments



**R.E. Dimond**  
& Associates, Inc.  
Consulting Engineers

ADDENDUM NO. 03

TIREY HALL ART STORAGE  
INDIANA STATE UNIVERSITY  
TERRE HAUTE, IN 47809

D&A # 11077

October 18, 2013



Daniel E. Dimond, P.E.

---

This Addendum issued prior to bidding, alters, amends, corrects or clarifies the Proposal Documents to the extent stated herein and does hereby become a part of the Proposal Documents, and will become a part of the Contract Documents of the successful bidder.

---

**DRAWINGS**

1. Drawing M601 Schedules and Details – Mechanical

a. Steam Coil Schedule

i. SHC – 1 – Manufacturer & Model

1. The model listed refers to a freeze proof coil with a distribution tube inside the coil fin tube. A freeze proof coil is not required. A standard steam coil without distribution tubes is acceptable.

END OF ADDENDUM